









### Rehabilitation / Complete Street Project (04-2Q520)

PRESENTED BY CALTRANS
MAY 10, 2023

## 2Q520 - PROPOSED PROJECT

PROJECT LOCATION (SR 29 - from I-80/SR 29 separation to Napa County Line)



#### SCOPE OF WORK

#### Rehabilitation of Pavement

- ► Cold Planing (0.25')
- Overlay (HMA 0.1' and RHMA 0.15')
- Pavement/ crosswalk striping

#### **Complete Street Elements**

- Class II/ IV bike lanes
- Lane Reduction
- Modify traffic signals
- Upgrade Curb ramps
- ► Curb extension Bulb outs/ Drainage modification
- ► Landscaping/Irrigation/Erosion Control
- Street Furnishings


# 2Q520 - Facts

- Project Initiation Document (PID) was approved in June of 2019 to rehab SR 29 from SR 29/ I-80 separation to Sol/Napa county line (PM 0.0-6.0) and added to 2020 SHOPP for a Con Capital of \$24.058 Million.
- Scope included Capital Preventive Maintenance (CAPM) along with some Complete Streets elements including curb ramps, and recommended further studies to incorporate additional improvements within the City downtown area.
- ▶ In collaboration with STA and City of Vallejo through Complete Street Reservation Proposal, Caltrans approved a Supplemental PID in May of 2021 for additional complete elements. Con Capital in SHOPP funds was increased to \$26.759 Million and \$721,000 funds are anticipated from STA/City of Vallejo for landscape/Irrigation/Controllers/benches.
- Added scope included Class II/IV bike ways (Sequoia Ave to Curtola Pkwy and Redwood St to Lewis Brown Rd), 57 Ped-scale LED light fixtures/36 Curb Extension-bulb outs/widen sidewalk (Pennsylvania St to Alabama St), Conflict zone green paint, lane reduction supported by feasibility studies, landscape/Irrigation and street furnishings.

# 2Q520 - Facts

- During Project Approval & Environmental Document (PA&ED) phase, Caltrans conducted traffic studies and preliminary Engg evaluation.
- Project is divided into 3 distinct segments:
  - South Segment (From Maritime Academy Dr to Curtola Parkway)
  - ▶ Middle Segment (From Curtola Parkway to Mississippi St)
  - North Segment (From Mississippi St to County line just north of Mini Dr)
- Project is approved on 5/9/2023 (T)
- ▶ TOAR is under approval process

# SR-29 South Segment Maritime Academy Dr to Curtola Pkwy




#### Project segment features:

- Buffered Class IV bike lanes
- Reconstruct all curb ramps to meet the latest ADA requirements
- Updated crosswalk striping
- Pavement rehabilitation

#### SR-29 South Segment - Maritime Academy Dr to Curtola Pkwy


- ▶ Project segment features:
- Buffered Class IV bike lanes
- Reconstruct all curb ramps to meet the latest ADA requirements
- Updated crosswalk striping
- Pavement rehabilitation



# **SR-29 Middle Segment**

## Curtola Pkwy to Mississippi St


Pavement rehabilitation



Updated crosswalk striping/ Ped Scale LED features

#### SR-29 Middle Segment - Curtola Pkwy to Mississippi St

- ▶ Project segment features:
- Lane reduction with two way left turn lane
- Class II bike lanes
- Curb extension bulb-outs for shorter ped crossings & traffic calming
- Reconstruct all curb ramps to meet the latest ADA requirements
- Updated crosswalk striping/ Ped Scale LED features
- Pavement rehabilitation




#### SR-29 Middle Segment - Curtola Pkwy to Mississippi St


- ▶ Project segment features:
- Lane reduction with two way left turn lane
- ▶ Class II bike lanes
- Curb extension bulb-outs for shorter ped crossings & traffic calming
- Reconstruct all curb ramps to meet the latest ADA requirements
- Updated crosswalk striping/ Ped Scale LED features
- Pavement rehabilitation



#### SR-29 Middle Segment - Curtola Pkwy to Mississippi St



# SR-29 North Segment Mississippi St to County Line




#### Project segment features:

- Buffered Class IV bike lanes
- Reconstruct all curb ramps to meet the latest ADA requirements
- Updated crosswalk striping
- Pavement rehabilitation
- Landscaping/ Erosion Control

#### SR-29 North Segment - Mississippi St to County Line

- ▶ Project segment features:
- Buffered Class IV bike lanes
- Reconstruct all curb ramps to meet the latest ADA requirements
- Updated crosswalk striping
- Pavement rehabilitation
- Landscaping/ Erosion Control







# City of Vallejo contribution



- Landscaping (street/ Median)
  - **▶** \$217,000 \*
- ► Irrigation/Controllers: \$350,000\*
- Street Furnishings (Benches/ Bike racks/trash cans): \$150,000\*
- ▶ Total Estimate \$721,000





\* Subject to final design in PS&E Phase



### Funding, Construction Capital, and Schedule

#### **Funding/ Estimate**

- ► SHOPP funds: \$26,759,000
- City of Vallejo's contr \$721,000
- ► Total avail funds: \$27,480,000
- Engineer's Estimate
- Con Capital (PAED): \$29,549,000
- ► Cost Overrun: \$2,060,000

#### Schedule

- ▶ PAED- May 2023
- ▶ Ready to List- Dec 2024
- ▶ Begin Construction: June 2025
- Construction Complete: June 2027

# 2Q520 - Rehab/Complete Street Project



Sindhu Kurup

Caltrans, District 4

Regional Project Manager, (Solano County – D4)

(510) 715-7920

Leslie Gould

Solano Transportation Authority

Assistant Project Manager

(707) 399-3219